Edtion and Public Health **(194 7) Department.**

Ms. **SERIES.**

G.O. NO. 2482 Edn.

2482

Dated 18-11-1947

[Despatch Abstract.]

Government. Mangalore-Improvements to playgrounds-Deferred.

Education Department.

From

Dr. S.R.U.Savoor, M.A., D.Sc., I.E.S.,
Director of Public Instruction, Madras.

To

The Secretary to Government,
Education & P.H.Department, Madras.

Rc.No.2049 G3/47 dated 25-9-1947.

Sir,



Sub: Buildings - Government College, Mangalore
Improvements to playgrounds - Plan and
estimate for Rs.20,000/- approval - requesting.

In submitting herewith a plan and an estimate for Rs.20,000/- for the work cited above, viz. improvements to the playgrounds of the Government College, Mangalore, I have the honour to request that Government may be pleased to accord their administrative approval to the scheme and provide necessary funds in Part II of the Budget Estimate for 1948-49.

2. The nature of, and the necessity for the work, have been explained at length in the report accompanying the estimate, from which it may be seen that the work is quite essential and very urgent.

for Director of Public Instruction.

Copy to G Section.

Report to accompany the approximate estimate for "Improvements play grounds, Government College, Mangalore."

Est. Rs.20,000/-

The accompanying Estimate is prepared as per requisition of the Principal, Government College, Mangalore vide his Nos. dated 7-5-1947 and 14-6-1947.

2. The Hockey (or football) field of the Government College is situated adjacent to and in rear of the Wenlock Hospital, Compound. The Municipal main road drain 20 size suntype which runs along the compound wall of the Government College enters the Hospital compound and ends abruptly there. Vide site plan enclosed. This storm water has deeply eroded the ground very much here. The earthen drain thus formed runs along the barbed wire fencing for some distance and enters the hockey field. Owing to heavy rains during the monsoon, the hockey field gets eroded and consequently involves frequent attention and repairs. Further the drains from the Nurses quarters and especially T.B.Ward dispose of the water etc. into the earthen drain (referred to above) and this water stagnates along the drain close to the fence involving great risk to the students as the ball during games rolls into the drain. At times the balls enter the T.B. land area also as there is only a barbed wire fencing.

3. The recently acquired strip of land on the eastern end of the hockey field is in a very low level drains itself here. A big natural drain has thus formed and has become a source of nuisance and danger during games.

On the southern side of the Hockey field there is twisted wire fencing of the C.I.R.Grounds which affords little protection against tress-passers who enter the Hockey field and go to the main road through the Hospital making suitable entry in the barbed wire fencing.

4. To remedy all these, the following improvements are proposed in this estimate

p.t.o.

1) Constructing a masonry drain 2-6" size sun-type on the northern side of the Hockey field (on the hospital side) in continuation of the existing masonry drain of 2'-0" size.

2) Constructing masonry compound wall 9" thick and 5'-6" high with intermediate pillars at 10' centres, including necessary foundations etc. in place of the existing barbed wire fencing north of Hockey field.

3)a) Earth work excavating in hard gravelly soil conveying and filling up low ground inclusive of all leads and lifts consolidation levelling etc. complete.--

) Constructing a masonry drain in place of the existing natural drain including provision of cover slabs.

4) Removing the existing barbed wire fencing with R.C.posts on the north side of hockey ground and refixing the same on the southern side with necessary new foundations etc. complete.

II. The general playground (or cricket field) of the College is situated in rear of the Taluk Office Compound. The storm and drain water from the taluk office, drains into this playground through weepholes in the masonry compound wall.

Owing to heavy rains during the monsoon period the playground gets eroded by the storm water and involves constant attention and repairs. Further due to the continued heavy erosion, the foundations of the compound wall have got scoured and exposed on the playground side.

Apart from this, the playground has no protection on the southern side, abutting the road leading to the Railway station, against trespassers who commit all sorts of nuisance etc.

To remedy these, the following improvements are proposed in this estimate.

5. Constructing a masonry drain 1-0" size sun type west of play ground (on the Taluk Office side) to dispose of the sorm water direct into the municipal earthern drain along the road margin.

6. Constructing a masonry compound wall 9" thick and

5'-6" high with intermediate pillars at 10' centres including necessary foundations etc. complete, on the sourthern side of the playground.

The unit rates adopted in this estimate for the various items of works are obtained from detailed estimates of similar works, or Mangalore town under execution or sent up for sanc

A site plan showing all the proposals is herewith

C

Sub: College - Govt., Mangalore - Improvement playgrounds - Plan and estimate - Part II Sc

1c f.c-no.76886 From the D.P.I. No. 2049 G3/47 dated 25.9.4

The proposal is to ef
certain improvements to the playgrounds
Govt. college, Mangalore. The D.P.I has forw
a site plan and an estimate amounting t
Rs 20,000/ for the work (the approval of the Govt.) the need for pushi
through the improvements in question urgent
is explained in the report accompanying th
estimate. In the circumstances stated ther
the proposal may be accepted, and provis
for the ~~xxxxx~~ expre made in Part II of the budg
for 1948-49.

2. The remarks of P.W.D. an
finance may be invited u.o

17.10.47

H.I.o.76886-1/47A dated 20-10-47

DEPUTY SECRETARY TO GOVT. 21 OCT 1947 6093 PUBLIC WORKS DEPARTMENT

P.W.D.

This deptt may agree to the proposals of the E&H Deptt and the file passed on Finance Deptt.

21/10/47

D.U.o No. 6083 C/47-1 28-10-47

NATIONAL DEFENCE 64025 BE II 28 OCT 1941 FINANCE

Financed (B.E II)

CF

Part II Scheme for 1948-9

Improvements to the playgrounds of the Govt. College Mangalore. — Cost Rs 20,000 (non-recurring)

The D.P.I. has submitted proposals for effecting certain improvements to the playgrounds of the Govt. College, Mangalore, at an estimated cost Rs 20,000. The nature of and the necessity for the work has been explained in the report accompanying th estimate. (Pp. 2-3 C f.)

In view of the stringent need for economy, ...t war development Schemes, Schemes relating to ...ve Food', remunerative Schemes and Schemes ...e imperatively and immediately essential ... proper running of the departments are to ...sidered as Part II Schemes for 1948-9 ...Scheme in the present case does not fall within ... of the above classes, Finance may advise ...t be deferred. If the E. & P.H. Department ... press the proposal, they may be requested to ...ders in circulation including H.M. Finance and H.P. ...ver this will be included for consideration as a ...heme for 1948-9 or not.

The work is no doubt a desirable one, but ... does not seem to be imperatively and ...mediately essential. It also involves cost ... buildings (Compound walls etc.). H.P.M. ...ested that all building schemes should be deferred as far as possible. In the circumst... Finance may advise that the work may be deferred.

If E & P.H. wish to press the proposal, they may take action as indicated at A above

4.11.47

4-11

Dr and P.H.

for orders whether in the circumstances ... by Finance the proposal may be deferred. ...